## TUMKUR DIVISION.

277

*Notification dated 5th May 1906.*

Rupees 150 (one hundred and fifty only) due to contractor Ranganna on account of earnest money deposited by him for restoring Chikmalur tank has been outstanding in the accounts of this office since July 1905. It is hereby notified that if the party does not present himself in the Executive Engineer's office at Tumkur to receive payment within a period of one month from the date of publication of this notification, the amount will be credited to Government as unclaimed deposits.

C. MADAVA RAO,
*Executive Engineer.*

## MYSORE DIVISION.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 15th June 1906, for restoring Kagalwadi tank, Registered No. 48, Chamrajnagar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1907.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kagalwadi tank, Registered No. 48, Chamrajnagar"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate for repairing the damaged portion of Kagalwadi tank, Registered No. 48, Chamrajnagar Taluk.

| Items of work | | Per | Quantity |
|---|---|---|---|
| Bund R. L. 56·00— | | | |
| | Earthwork ... ... ... ... | C. yd. | 2,826 |
| | Turfing ... ... ... ... | S. yd. | 12,958 |
| | Rough stone work, new ... ... ... | C. yd. | 2,308 |
| | Old rough stone with fresh jelly... ... ... | „ | 659 |
| | Gravel backing ... ... ... ... | „ | 743 |
| | Gravel to top of bund ... ... ... | „ | 540 |
| Waste-weir No. 1— | | | |
| | Burnt brick in surki mortar ... ... ... | C. ft. | 1,827 |
| | Burnt stone slabs (old) ... ... ... | S. ft. | 522 |
| | Rough stone work, new ... ... ... | C. yd. | 481 |
| | Do do old ... ... ... | „ | 524 |
| | Rough stone new, jelly packing ... ... | „ | 389 |
| Waste-weir No. 2— | | | |
| | Burnt brick in surki mortar ... ... ... | C. ft. | 232 |
| | Burnt stone slabs, old .. ... ... | S. ft. | 93 |
| | Rough stone work, new ... ... ... | C. yd. | 117 |
| | Do do old ... ... ... | „ | 88 |
| Waste-weir No. 3— | | | |
| | Burnt brick in surki mortar ... ... ... | C. ft. | 232 |
| | Burnt stone slabs, old ... ... ... | S. ft. | 93 |
| | Rough stone work, new ... ... ... | C. yd. | 84 |
| | Do do old ... .. ... | „ | 100 |

V. V. KARVE,
for *Executive Engineer.*